

USACE 408 Submittal Package

Define project
Analyze impact
Certify no adverse impact
Define timeline
Create EAP template
Summarize O&M impacts
Sponsor's statement

You Want What By When?

USACE 408 Schedule

- Developed Critical Path Schedule
- Responsible Parties on Critical Path
 - Thiele Geotech (Boring/Lab Testing)
 - Stanley Team Levee Stability / Settlement, River Hydraulics
 - Iowa DOT Roadway Design


 - USACE (5 Interim Submittals, 408)


 HDR Levee Design, Construction Management, O&M Addendum, Levee Certification
 - Levee Sponsor Concurrent review and approval of 408

You Want What By When?

USACE 408 Schedule

- Results
 - Start Geotechnical Borings / Design -5/1/2019
 - Preliminary Design Plans 5/14/2019
 - Letting Plans to DOT Contracts 6/15/2019
 - 408 Authorization from USACE 7/12/2019





23

You Want What By When?

USACE Project Quote

To facilitate USACE review and approval, IDOT quickly set up meetings with USACE to coordinate the project. They identified critical design elements and milestones, contacts within the USACE team, and the IDOT team so questions could be answered quickly. The IDOT team and USACE team continued this coordination throughout the permission process. There were also "over the shoulder review points" completed to allow real time feedback from the USACE team to the IDOT team. This all ensured that the appropriate reviews occurred and USACE levee design criteria was met.

Ensuring flood risk reduction during construction required considerable planning and sequencing by IDOT. This would have been challenging during ordinary years, but in 2019 the Missouri River at the project site was above flood stage for 270 days. The sequencing, coordination and communication during construction allowed for confidence from the USACE team, the Levee Sponsors, and the community that flood risk reduction was continuous.


24


You Want What By When?


Key Levee Takeaways


- USACE Trust and Pre-Submittal Review
- Strict Adherence to CPM Schedule
- Dewatering Issues
- Early Coordination Levee Staged Construction
- Conservative Design to Start
- Fiber Optic Utility Issue
- Intensive Design Coordination
- Levee Construction Management / Certification














31

You Want What By When?

Key Bridge Takeaways

- Concurrent Preliminary and Final Design
- Continuous Coordination with Other Disciplines
- Provide Contractor Flexibility
- Plan for Challenging Site Conditions
- Keep it Simple Repetitive & Conservative Design
- Utilize BIM model for visualization and over the shoulder QC
- Keep moving forward



33

You Want What By When?

Checking In with Contractors

- Two meetings with AGC
 - May 8, 2019
 - June 3, 2019
- Two purposes
 - Get feedback on the design goals: timeline, ease of construction
 - Inform about contracting peculiarities: unsigned plans, pending permits, short advertising period

34
You Want What By When?

Addressing Risk

- Bonus for opening the floodway ***
- Deferred completion date when waters exceeded a given elevation
- Advertising unsigned plans/addressing quantity changes
- Delays in permitting







