



Agenda

INTRODUCTIONS

- Matt Rasmussen (Schemmer)
- Cliff Rhoads (Jasper)

PROJECT OVERVIEW

FINGER JOINT REPLACEMENT

CLOSED DRAINAGE SYSTEMS

FIELD CHALLENGES

BID ESTIMATION & STAFFING

FIELD VERIFICATION

CONSTRUCTION


Q & A



Project Overview

EXISTING BRIDGES

- Twin 1763'-0" x 64'-0" Min. Width
Continuous Welded Plate Girder Bridge
- Two On/Off-Ramp Multi-Span Bridges



Project Overview

PROPOSED REPAIRS



- Strip Seal Joint Replacements at Abutments
- Replace Sliding Plate Joints with Finger Joints at Cantilever Roller Joints
- General Concrete Repairs
- Add Closed Drainage System
- Partial Approach Replacement



Closed Drainage System

DESIGN CONSIDERATIONS



- Locations/Nearby Concrete Repairs
- Relative Movement Between Superstructure and Piers
- Length of Support Available from Deck
- Conflicts with Existing Structure and Site
- Construction Tolerances
- Remaining Life of Structure



Closed Drainage System

DESIGN CONSIDERATIONS


- Locations
 - Existing Sliding Plate Joints (Replaced)



Closed Drainage System

DESIGN CONSIDERATIONS


- **Locations**
 - Existing Sliding Plate Joints (Replaced)
 - *Downspouts (New)*



Finger Joint Replacement

DESIGN CONSIDERATIONS


- Alignment on a Horizontal Curve
- Superelevation
- Large Skew
- Cantilever Roller Expansion Joint
- Movement Range Required
- Construction Tolerances
- Remaining Life of Structure



Finger Joint Replacement

DESIGN CONSIDERATIONS


- Alignment on a Horizontal Curve
- Superelevation
- Large Skew
- Cantilever Roller Expansion Joint
- Movement Range Required
- Construction Tolerances
- Remaining Life of Structure



Field Challenges

CLOSED DRAINAGE SYSTEM INSTALLATION


- **Epoxy/Grout System**
 - Both Vertical & Horizontal Applications Needed



Field Challenges

CLOSED DRAINAGE SYSTEM INSTALLATION



- **Epoxy/Grout System**
 - Both Vertical & Horizontal Application Needed
- **Pre-Emptive Construction Guidance**
 - Adjustments of Drainage Pipe Grade in the Event of Conflicts with Existing Structure



Field Challenges

FINGER JOINT INSTALLATION

- **As-Builts Did Not Match Field Conditions**
 - End Plates at Cantilever Roller Joint
 - Bolt Locations for Finger Joint Support Brackets



Field Challenges

FINGER JOINT INSTALLATION

- As-Builts Did Not Match Field Conditions
 - End Plates at Cantilever Roller Joint
 - Bolt Locations for Finger Joint Support Brackets
- Modification of Exist. Steel Girders
 - Coping of Stiffeners
 - Painting Exposed Steel

Field Challenges

FINGER JOINT INSTALLATION

- As-Builts Did Not Match Field Conditions
 - End Plates at Cantilever Roller Joint
 - Bolt Locations for Finger Joint Support Brackets
- Modification of Exist. Steel Girders
 - Coping of Stiffeners
 - Painting Exposed Steel

Field Challenges

FINGER JOINT INSTALLATION

- As-Builts Did Not Match Field Conditions
 - End Plates at Cantilever Roller Joint
 - Bolt Locations for Finger Joint Support Brackets
- Modification of Exist. Steel Girders
 - Coping of Stiffeners
 - Painting Exposed Steel
- Pre-Emptive Construction Guidance
 - Additional Fill Plates
 - Long Slotted Hole Length Increase
 - Plate Washers
 - Modifications to Finger Joint Bent Plates
 - Modifications to Finger Joint Support Brackets

Linn County I-380 Bridge Repair Project

- Letting Date: March 21st, 2023
- Contract Amount: \$2,525.808.50
- Late Start Date: July 5th, 2023
- Work Period: (4) weekends from Friday 7:00 PM – Monday 5:00 AM
- Liquidated Damages: \$250.00/Hour
- Finger Joint Supplier: RJ Watson, Inc., Alden, NY
- Finger Joint Material Cost: \$456,067.00 (172 LF)
- Lead Time: Shop Drawings (6 weeks), Fabrication (20 weeks)

Bidding, Planning, & Scheduling

Bidding Concerns

- Finger joint material lead time
- Significant manpower needed each weekend
- Employees potentially quitting for working long hours
- Other projects going on at the same time (12 projects)
- Equipment mobilization each weekend
- Weather delays during weekend work
- Process to install finger joints
- Time required to install finger joint (start to finish)
 - *Modular joints typically take 7-10 days*
- Time required to install extrusion joint (start to finish)
 - *Typically take 4-6 days*
- Concrete cure time
 - *C-4 mix cure time is typically 36 +/- hours*
- Potential costs incurred if finger joints do not fit properly and work does not get completed in time each weekend
 - *Penalty (\$250.00/HR)*
 - *Fabrication costs*
 - *Labor costs*
 - *Reputation*

Bidding, Planning, & Scheduling

Planning (Prior to Construction)

- Transparency with DOT about lead time (26+ weeks)
 - *Best case scenario for starting late October 2023*
- Planning meetings with DOT, Schemmer, and RJ Watson
 - *Discussions related to project scheduling, traffic control staging, as-built drawings vs. field measurements, possible issues installing finger joints*
- Monthly planning meetings with crew supervisors
 - *Some excited for the challenge, some not so much*
- Weekly planning meetings with crew supervisors for 8 weeks prior to start date (September 2024)
- Added project specific incentive pay for all employees
 - *\$20/Hr for night crews*
 - *\$15/Hr for day crews*
 - *In addition to Zone 1 prevailing wages (overtime)*
- Submitted new mix design to DOT to accelerate cure time
 - *O-4WR with ½" coarse aggregate*
 - *Allowed by DOT – considered small volume repair per specs*
 - *Achieved maturity in 16 hours +/-*

- First priority was to field measure I-380 NB and SB bridges
 - *Needed to verify as-built dimensions*
- Scheduling discussions with traffic control subcontractor and material suppliers
- Weekly meetings to discuss manpower needs
 - *Work during week prior to weekend work*
 - *Friday (night work)*
 - *Saturday (day work)*
 - *Saturday (possible night work)*
 - *Sunday (day work)*
 - *Sunday (possible night work)*
- Weekly meetings to discuss equipment mobilization
 - *Equipment mobilizing from multiple jobsites*
 - *Equipment rental needs*
- Daily/Weekly meetings with DOT for work progress updates and changes

[illegible]

Weekend #2 (September 20th-22nd)									
Friday Night Crews			Saturday Crews			Sunday Crews			
North Abcumb	Finger Joint	South Abcumb	North Abcumb	Finger Joint	South Abcumb	North Wilson	Sunday Crews		
Josh Rogers	Angie Chaventa	Emmanuel Galvez	Jeremy Holland	Curly Wilkins	Joel Haskin	Nick Wilson	Ezzy Collier		
Miguel Camacho Galvez	Emmanuel Galvez	Joan Rendon Garcia	Francisco Garcia	Francisco Garcia	Joel Haskin	Dylan Edmonds	Rodrigue Volquez		
Braulio Moreno	Joan Jose Chaventa Perez	Joan Argando Aranda	Joan Miguel Fontana	Heider J Gomez Olmos	Joan Obispo Madrid	Pat Edmonds	Pat Edmonds		
Marcelo Carlos Chaventa	Mauricio	Francis Ortega-Morino	Cesar Fontana	Tony Nunzio	Joel Cabrera Valdivinoso	Garet Blankenship			
Salvador Caldeira	Joan Carlos Reynoso Garcia	Reginald Bales	Luis F Hernandez Ortiz	Agustin Garcia Ordez	Agustin Garcia Ordez	Mandy Clark			
Andrew Martinez	Andrew Buenavista	Angel Galvez	Miguel P. Huesca Chaventa	George Zanera Mendez	Jeffrey Villalaz	Joan C Cartson			
John Siskus	Joel Garcia Buenavista	Alvin Correa	Luis Manuel Reinaiza Garcia	Rodrigue Vazquez	Sul Marie Martinez	Joseph Daniel Martinez			
Joel Reynoso Garcia	Joel Reynoso Garcia				Adrian Bilez Valdivinoso	Vincent			
Carlos Magana	Carlos Magana					Arthur Blankenship			
Joan Carlos Tapia	Joan Carlos Tapia					Layne Scom			
Finger Joint Forming Crew #1 (On Ground)									
School Lift #1:			Samilo Hernandez						
School Lift #2:			Joan Manuel Garcia Garcia						
Booms Lift #1:			Arturo Mendez						
Booms Lift #2:			Yolani Edmonds						
Booms Lift #3:			Joan Gomez Chaventa						
Booms Lift #4:			Joan Garcia (Chung)						
Finger Joint Forming Crew #2 (On Ground)									
Onsite			Pedro Figueira Hernandez						
David Andrade			Joan J Virgen Caldeira						

Friday Night: 24

Saturday: 35

Sunday: 12

Total: 71

Changes from Weekend #1

Reduced personnel doing removals at North and South Abouth Aboints

Added personnel forming finger joint in lifts and on ground

Added lift equipment for forming finger joints

[illegible]

Field Measuring for Finger Joint Fabrication and Installation

[illegible]

Field Measuring for Finger Joint Fabrication and Installation



Construction

Beam Coping and Painting

- Majority of work took place prior to weekend construction
- Measured girder temperature with infrared thermometer and stopped work as necessary
- Sherwin Williams Dura-Plate 235
 - Fast drying epoxy paint (2 hrs at 77 degrees)



Construction

Concrete Demolition Process

- Saw top and bottom side of concrete first for clean edges
- Lots of jackhammering and hard work
- Torched existing slide plate joint into small pieces and removed with excavator
- No easy way to do removal process



Construction

Finger Joint Installation

- Pre-set joint opening dimension based on weekend temperature
- Used (2) Komatsu 138 excavators to set in place (Crane on standby)



Construction

Finger Joint Installation


- Extremely tight fit and difficult to make adjustments for the skew angle



Construction

Finger Joint Installation


- Used lots of steel shims to account for variable height of steel girders
- Joint setting height was critical for welding joint between stages and to ensure joint was installed 1/4" below bridge deck surface



Construction

Rebar, Formwork, and Concrete

- Slow process to install rebar with limited space
- Difficult formwork and bracing process working from lift equipment



Construction

Rebar, Formwork, and Concrete

- Difficult formwork and bracing process working from lift equipment



Construction

Rebar, Formwork, and Concrete

Poured barrier wall sections with cover plates in place to allow barrier wall to be poured integral with deck concrete

Weekend #1 Concrete Pour Time: 11:30PM Sat (Cure time: 3:30pm Sun)

Weekend #2-4 Concrete Pour Time: 5:30PM Sat (Cure time: 9:30am Sun)

Sunday Work: strip forms, watertight testing, equipment de-mobilization, final cleanup, restoring traffic control



Linn County I-380 Bridge Repair Project

Summary

- Great weather with no rain over (4) weekends
- Crews were excited for the challenge, wanted to prove work could be done on time
- Made critical adjustments after first weekend for better performance
- Project planning and scheduling was critical to project success
- Open communication between DOT, Schemmer, and Jasper was greatly beneficial
- Very stressful project, built confidence to take on more complex projects in the future

Complex Bridge Rehabilitation on I-380 Viaduct: Overcoming Design and Construction Challenges in Cedar Rapids



